

| CONSTRUCTION          |  | COMPLIANCE  |   |
|-----------------------|--|---|---|
| <b>Materials</b>      | Grade-A "One-Trip" Shipping Conex  | <b>OSHA</b>   | 1910.106  |
| <b>Door</b>           | 90 minute fire-rated steel door with panic bar and closer                                  | <b>NFPA</b>   | All booths are built meet NFPA 1, NFPA 30, NFPA 33, NFPA 58, NFPA 70, NFPA 91 |
| <b>Penetrations</b>   | Utility plate with pre-punched holes and seal offs to accomodate additional equipment.     |   |   |
| BOOTH SIZE            |  | ELECTRICAL  |   |
| <b>Dimensions</b>     | 40' X 8' X 8'6"  | (4) 115 volt rated 20A wall recepticles, (2) wall switches, (4) ceiling mounted LED lights, (2) Variable Frequency Drives, (1) UL-Listed 24x24 Control Panel, 3/4" rigid conduit<br><br>*Additional wall switches and recepticles can be added at an additional price |   |
| <b>Square Footage</b> | 320 sq/ft  |   |   |
| <b>Door Size</b>      | 30-70 egress door  |   |   |
| AIR SYSTEM            |  | HVAC  |   |
| <b>Fans</b>           | (1) 850 CFM fan<br>(1) 5600 CFM fan  | 100 % Outside Sourced Air   |   |
| <b>ACH</b>            | Base flow rate - 14 air changes per hour<br><br>Purge flow rate - 120 air changes per hour |   |   |
| ALARMS                |  | TURN-KEY  |   |
| <b>Gas Sensor</b>     | (1) Honeywell Sensepoint XCD gas monitor   | This unit is "Plug-n-Play". Set it, anchor, power and water ready   |   |
| <b>Audible Alarm</b>  | (1) audible alarm sounds @ 20% lower explosive limit                                       |   |   |